JC HUNTER
TECHNOLOGIES

3200 S. Wadsworth Blvd.
Lakewood. Col. 80227
Ph. 626 7789763
PROPOSAL

PROPOSAL SUBMITTED TO:	PER PLAN & SPECS:
Owen-Ames-Kimball Co. - Jess Matias	YES - 2026 Permit Drawings + Project Manual Vol 1 & 2
PROJECT NAME:	**ARCHITECT:**
CR CITY HOTEL (new 4-story hotel, Type IIIB, wood framed)	Meridian 105 Architecture
PROJECT ADDRESS:	**DATE OF PLANS:**
415 PERRY STREET, CASTLE ROCK, CO 80104	Arch. / Struct. 04-22-2026 (Issued for Permit); MEP 06-01-2026
DATE OF PROPOSAL:	**ADDENDUM:**
11-06-2026	None reviewed [TO BE CONFIRMED]
PHONE NUMBER:	**E-MAIL:**
[TO BE COMPLETED]	[TO BE COMPLETED]

Scope of Work:

We propose to supply the material, labor, and equipment necessary to complete the work in accordance with the plans

(Please take special note of the scope description; we are not required to perform any items or tasks not specifically listed)

1.- Division of work: DRYWALL & FINISH LEVEL 4, C-H SHAFT WALLS, CEILING SUSPENSION.

INCLUDED (quantities from the take-off rev3 FINAL: net and purchase = net + waste, with their sheets):
- Ceiling / soffit track (size per source, see Where it comes from): 2,414.06 LF net / 2,776.17 LF purchase [1/A7.31, 2/A7.31, 4/A7.31, 5/A7.31, 7/A7.31, 1/A7.23 (+7 more)]
- Carrying channel (ceilings): 158.76 LF net / 182.57 LF purchase [1/A2.02, 7/A7.23, 1/A3.02, 2/A7.05, 13/A7.16, 1/A5.06 (+5 more)]
- Hanger wire: 465.72 LF net / 535.58 LF purchase [1/A2.02, 7/A7.23, 1/A3.02, 2/A7.05, 13/A7.16, 1/A5.06 (+15 more)]
- 5/8" gypsum board, Type X: 85,007.29 SF net / 90,107.73 SF purchase [1/A5.06, 3/A7.45, 1/A5.08, 1/A7.30, 3/A5.04, 1/A7.31 (+94 more)]
- 5/8" gypsum board, Type X W.R. (water resistant): 27,111.73 SF net / 28,738.43 SF purchase [1/A2.02, 2/A7.00, 6/A7.00, 10/A7.00, 2/A7.05, 4/A7.05 (+52 more)]
- USG drywall suspension main tee DGLW26: 1,706.50 LF net / 1,962.47 LF purchase [1/A2.02, 7/A7.23, 1/A3.02, 2/A7.05, 13/A7.16, 1/A5.06 (+4 more)]
- USG drywall suspension cross tee DGLW424: 5,119.67 LF net / 5,887.62 LF purchase [1/A2.02, 7/A7.23, 1/A3.02, 2/A7.05, 13/A7.16, 1/A5.06 (+4 more)]
- USG angle molding DGWM24: 2,170.44 LF net / 2,496.01 LF purchase [1/A2.02, 7/A7.23, 1/A3.02, 2/A7.05, 13/A7.16, 1/A5.06 (+4 more)]
- 5/8" cement board (tile base): 3,593.29 SF net / 3,808.89 SF purchase [1/A2.02, 6/A7.02, 8/A7.03, 9/A7.03, 1/A2.03, 1/A2.04 (+2 more)]
- Resilient channel - printed product (see Where it comes from): 18,020.10 LF net / 20,723.12 LF purchase [1/A2.02, 7/A7.23, 1/A3.02, 2/A7.05, 13/A7.16, 1/A5.06 (+7 more)]
- METAL trim - corner bead, casing bead, shadow molding, gypsum edge trim: 3,871.99 LF net / 4,452.79 LF purchase [08/A9.05, 1/A8.02, 2/A8.02,

3/A8.02, 1/A7.31, 1/A7.23 (+13 more)]
• Control joint, gypsum board walls (ASTM C840, 30 ft max): 831.48 LF net / 956.20 LF purchase [A2.01, A0.06, C840, A2.02, A2.03, A2.04]
• 5/8" gypsum board, Type C (ceiling): 19,715.57 SF net / 20,898.50 SF purchase [4/A5.05, A3.01, A0.08]
• 1" gypsum shaftliner panel, Type X (C-H shaft wall): 1,317.34 SF net / 1,396.38 SF purchase [1/A7.50, 5/A5.04, 7/A9.03, 1/A4.04, 2/A4.04, 1/A5.08 (+10 more)]
• 5/8" exterior gypsum sheathing, Type X: 17,746.71 SF net / 18,811.51 SF purchase [08/A9.05, 8/A9.05, 6/A9.03, 5/A5.04, 1/A4.04, 5/A6.02 (+21 more)]
• C-H stud 6" 20 GA (shaft wall) - printed (see Where it comes from): 1,150.33 LF net / 1,322.88 LF purchase [1/A2.03, 7/A9.03, 1/A2.04, A7.50, A0.06, U415 (+4 more)]
• J-runner 6" 20 GA (shaft wall top / bottom) - printed (see Where it comes from): 256.90 LF net / 295.44 LF purchase [1/A2.03, 1/A2.04, A7.50, A0.06, A2.02, A0.08]
• Joint compound, all purpose: 9,492.09 LB net / 9,492.09 LB purchase [driver = the board / stud / bottom track rows of this sheet]
• Joint tape, paper: 48,778.80 LF net / 48,778.80 LF purchase [driver = the board / stud / bottom track rows of this sheet]
• Level 4 finish on all interior gypsum board (09 29 00 3.6.E.4); board only on the wood-framed walls (framing by others).

1a. Gypsum board on the WOOD-framed walls (framing by others, Div. 06): 5/8" Type X per face and layers per type and rating (A0.06, A0.07, UL U379 / U301 / U341 / V337), 5/8" Type X W.R. at toilet / shower / janitor faces (A0.06 GN 11 / 12), 5/8" cement board at guest bath tile walls (GN 13), 5/8" Type X exterior gypsum sheathing per A0.07 XW rows.

1b. Ceilings: FS-1 5/8" Type C on resilient channel (A0.08, UL L546), RS-1 5/8" Type X on channel under the roof, GYP-1 / GYP-2 dropped ceilings on USG drywall suspension (main tee DGLW26, cross tee DGLW424, angle DGWM24, hanger wire), corridor bands, lobby coffers and stair soffit with ceiling / soffit track (7/A7.23, 2/A7.31, 11/A6.01).

1c. C-H shaft walls CH.6-2 (A0.06, A7.50, A9.03, UL U415): 6" 20 GA C-H studs @ 24" o.c., 6" 20 GA J-runner, 1" Type X shaftliner + 2 layers 5/8" Type X.

1d. Metal corner bead (09 29 00 2.5), control joints (A0.06 GN 15, ASTM C840), joint tape and compound, Level 4 finish.

NOT INCLUDED / EXCLUSIONS:

• Interior partition framing (studs + tracks): (Div. 06, R80f.1 / U-139). Metal framing only at C-H shaft walls (ALC-21).
• Exterior wall framing (CFMF): (Div. 06); interior board and exterior gypsum sheathing carried (ALC-07 / ALC-09).
• Parapet framing: (Div. 06); A0.01 / A0.02 / A8.02 parapet mentions are code / flashing.
• Headers, sills and jambs at openings: (Div. 06). Gypsum board returns at windows: see trim / returns.
• FRT plywood sheathing / substrate: wood (Div. 06): FRT plywood / LP Flameblock sheathing (A0.07, A0.08, A2.05, A7.30, A9.03, S5.01).
• Blocking (FRT wood / metal) for millwork and accessories: (Div. 06, U-139); no metal blocking printed.
• Framed openings (MEP, access panels, diffusers): framed openings for ducts / diffusers (standing order); no access panels in gypsum scheduled (A8.00, M1.01, M1.05, P4.00, P4.01, T0.01 legend).
• Acoustical sealant / sound attenuation: EXCLUDED in all projects (estimator standing order): no acoustical sealant row and no quantity
• Wood framing / blocking / sheathing (Div. 06): wood studs, plates, trusses, blocking, FRT plywood, LP Flameblock (A0.06, A0.07, A0.08, S-sheets): Div. 06 (U-139).
• Fasteners: screws, anchors, PAF: estimator standing order (U-053).
• Framed openings for ducts / penetrations: estimator standing order (R-ALC-03).
• ACT / wood slat ceilings: ACT-1 / ACT-2 / ACT-3 lay-in and WS-1 wood slat ceilings (A3.01-A3.04, A7.23, A7.31): other trades.
• Insulation: batt / mineral fiber / rigid insulation (A0.06, A0.07, A0.08).
• Plaster / wallcovering / paint: TF-1 plaster, vinyl wallcovering, P-1 / P-2 paint (A7.19).
• CMU / concrete walls: CM.x CMU and C.x cast-in-place concrete walls (A0.06, A6.00-A6.02): masonry / concrete trades.
• Separate-permit areas: grey toned area 'UNDER A SEPARATE PERMIT AND NOT IN SCOPE' (A2.01-A2.04); existing historic building (A0.00).
• Doors, frames, windows, hardware: A8.00 / A8.01 by others.
• Structural steel: kickers, clip angles, L3x3 angles: L3x3x1/4 KICKER at 4'-0" o.c. (S1.02, 5/S3.08) and CLIP ANGLE with threaded rods into masonry (S3.04, S3.08) are structural steel (Div. 05 12 00), by the steel fabricator.
• insulation (batt, sound batt, rigid polyiso, rigid board): estimator standing order: insulation always EXCLUDED
• Gypsum board & finish at the NON-rated retail-side faces of Retail 124 (A2.01 note 'BY FUTURE TENANT', RFI-05); L1 retail steel beam wraps by future tenant
• Area 'UNDER A SEPARATE PERMIT AND NOT IN SCOPE' (A2.01, RFI-06) and the existing historic building
• Screws, anchors, pins and power-driven fasteners (estimator standing order U-053)

• Screws, anchors, pins and power driven fasteners (estimator standing order: $ 0.00)
• Level 5 finish, FRP, access panels (none scheduled for our trade)
• Bonds, permits and fees; temporary utilities, dumpster, prevailing wages, shop drawings
• Addenda not reviewed in this pricing; anything not specifically listed in the INCLUDED scope

NOTE: PROPOSAL HOLDS GOOD ONLY FOR THE ITEMS AND QUANTITIES LISTED ABOVE (TAKE-OFF REV1 FINAL)

3.- Work Standard:

All work is to be completed in a workmanlike manner according to standard practices. Workers will remain on the job until completion of the project. The worksite will be cleaned daily and upon project completion. All agreements are contingent upon delays beyond our control.

4.- Limited Warranty:

The completed work shall carry a 1-year warranty on labor and materials. This warranty is in lieu of all other warranties, expressed or implied, and excludes consequential or incidental damages caused by accident or abuse, temperature changes, settlement, moisture, or cracks caused by expansion and/or contraction.

5.-	Insurance:
All employees are covered under blanket workman's comp, with liability and umbrella insurance policies.	

6.-	Touch-Ups:
Drywall & finishes: included on all work performed, limited to 1 hr per every 1,000 SF for quality issues; trade damage repairs tracked on work ticket. Finish level per GA-214 (Level 4).	

7.-	Others:
7.1. Work sequenced according to industry standards; out of sequence work and schedule delays require added cost. 7.2. Work days Monday - Saturday, 7:00 am - 5:00 pm (no overtime or night work included). 7.3. Price valid for thirty (30) days. Material pricing per FBM list prices read 11-05-2026.	

9.- Metal framing (C-H shaft walls) & ceiling suspension:	
	$51,000
9.a- Drywall & drywall finish Level 4:	
	$440,600
Total all trades:	
	$491,600
Taxes (8.81% template rate - to confirm for Castle Rock):	
	$43,310
Total including tax:	
	$534,910

****NOTE: items marked [RATE TO CONFIRM] / [PRICE TO CONFIRM] in the PRICING sheet are not in the totals.**

Acceptance of proposal:

The prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified.

Signature: _____

Date of

CLARIFICATIONS (decisions applied in the quantities):

Wood-framed building: all W / FW / DW / FI / XW types are wood studs (A0.06, A0.07) - board only; framing, blocking, FRT plywood by Div. 06.

RFI-10: WOOD / FURRED WOOD / DBL. WOOD sections print 5/8" TYPE X GYP BD. TYP. - Type X loaded on every interior face (09 29 00 2.3 A).

RFI-11: cement board at guest bath tile walls to 9'-0" (bath ceiling 8'-6" + 6"); rated Type X W.R. layers stay full height.

RFI-07: shaft walls carried as the A0.06 CH.6-2 row (6" C-H studs) - verify 7/A9.03, 8/A9.03 (4 3/4" overall assembly).

RFI-16 / RFI-14: C-H studs @ 24" o.c. (UL U415); resilient channel @ 16" o.c. (UL L546, 'spacing per assembly').

RFI-12: GYP-1 'metal suspension OR wood framing' - metal option carried (USG drywall suspension).

RS-1 ceilings under the roof: board type not printed - 5/8" Type X carried; channel carried in the resilient channel row.

RFI-05: retail faces of RATED assemblies stay loaded (1,033 SF); non-rated retail faces excluded (532.5 SF, by future tenant).

RFI-18: L4 corridor 412 cove carried along the corridor walls (typical 7/A7.23); L1 lobby ceiling carried at 11'-0", no step face.

Material prices: FBM (myfbm.com) list prices read 11-05-2026; exterior sheathing priced as 5/8" Type X gypsum sheathing 4x8.