JC HUNTER
TECHNOLOGIES

3200 S. Wadsworth Blvd.
Lakewood. Col. 80227
Ph. 626 7789763
PROPOSAL

PROPOSAL SUBMITTED TO:	PER PLAN & SPECS:
Elite Retail Services (Vivian Tran) / Elder-Jones, Inc. (Mason	YES - plans listed below (no project manual in the set)
PROJECT NAME:	**ARCHITECT:**
CONSUMER CELLULAR - YOSEMITE PARK SHOPPING CENTER	Sargenti Architects (project 15066-26)
PROJECT ADDRESS:	**DATE OF PLANS:**
8283 S. AKRON ST., SUITE 110, CENTENNIAL, CO 80112	10-15-2026 (90% set / permit set, 37 sheets)
DATE OF PROPOSAL:	**ADDENDUM:**
11-05-2026	Rev 2 Permit Set 11-04-2026 (Elite / Elder-Jones addenda 11-05-
PHONE NUMBER:	**E-MAIL:**
[TO BE COMPLETED]	[TO BE COMPLETED]

Scope of Work:

We propose to supply the material, labor, and equipment necessary to complete the work in accordance with the plans

(Please take special note of the scope description; we are not required to perform any items or tasks not specifically listed)

1.- Division of work: METAL FRAMING, DRYWALL & DRYWALL FINISH LEVEL 4, FRP (CSI Div. 05 40 00 / 09 21

INCLUDED (quantities from the take-off rev4 FINAL, net before waste, with their sheet):

- Bottom track 3-5/8": 192.84 LF [1/A500]
- Bottom track 6": 7.67 LF [1/A500]
- Top slip / deflection track 3-5/8" (2" deflection leg, walls to structure): 135.40 LF [1/A500, 4/A500]
- Top slip / deflection track 6" (2" deflection leg, walls to structure): 7.67 LF [1/A500, 4/A500]
- Top track 3-5/8" - standard (walls not reaching structure): 57.44 LF [1/A500, 3/A500]
- 6" metal stud (LF of material): 150.33 LF [1/A500, 1/A504]
- 3-5/8" metal stud (LF of material): 2,919.58 LF [1/A500, 3/A600]
- Header / metal stud box beam: 24.00 LF [2/A400, 2/A600]
- Hanger wire: 75.00 LF [2/A501, 1/A200]
- 5/8" gypsum board, MOISTURE RESISTANT: 18.67 SF [1/A504]
- 5/8" gypsum board, Type X: 4,293.90 SF [1/A500]
- 5/8" gypsum board, Type X W.R. (water resistant): 474.32 SF [1/A500, 2/A501]
- USG drywall suspension main tee DGLW26: 23.25 LF [2/A501, 1/A200]
- USG drywall suspension cross tee DGLW424: 53.67 LF [2/A501, 1/A200]
- USG angle molding DGWM24: 31.75 LF [2/A501, 1/A200]
- Clip angles and framing clips (see Where it comes from): 42.00 PCS [2/A500]

• Clip angles and framing clips (see Where it comes from): 62.00 PCS [3/A500]
• Nested inner runner at the deflection head (detail per Where it comes from): 143.07 LF [4/A500]
• Demolition - area of the element to demolish (SF = wall length x height / ceiling area, element area only): 2,250.70 SF [1/D100]
• Metal stud blocking at wall-mounted items (notes) - 20 GA metal strapping: 145.33 LF [2/A104, 1/A400, 1/A104, 3/A400, 3/A104, A103]
• Metal stud blocking at wall-mounted items (notes) - 20 GA track: 8.00 LF [5/A402]
• Metal stud blocking at wall-mounted items (notes) - stud blocking (per source): 42.00 LF [5/P501, A402]
• METAL trim - corner bead, casing bead, shadow molding, gypsum edge trim: 111.75 LF [A400, A100, A200]
• FRP panels: 148.33 SF [1/A504, A402]
• Control joint, gypsum board walls (ASTM C840, 30 ft max): 49.66 LF [1/A500]
• Metal stud brace to structure (size / gauge per the detail, see Where it comes from): 373.31 LF [3/A500]
• Hanger wire 12 ga - hanger count (one per hanger, height per room): 9.00 PCS [2/A501, 1/A200]
• PVC trim at the FRP - edge, inside corner, outside corner and division bar moldings (see Where it comes from): 138.16 LF [6/A502, 1/A504]
• Joint compound, all purpose: 344.66 LB [driver = the board / stud / bottom track rows of this sheet]
• Joint tape, paper: 1,771.15 LF [driver = the board / stud / bottom track rows of this sheet]
• Partition types A3, C3, D, E3 per 1/A500 (A100); Level 4 finish on all gypsum board (rule U-147).

1a. Metal framing: interior partitions A3 / C3 / D / E3 (1/A500), 20 ga tracks (2/A500, 3/A500), long-leg slotted deflection track + nested C channel (4/A500), top of wall braces 3/A500, door / cased opening headers 2/A600, metal strapping / track / stud blocking (1-4/A104, 5/A402, A402 note 4, 5/P501), drywall grid at the restroom C-1 ceiling (2/A501)

1b. Drywall & drywall finish Level 4: 5/8" Type X board per partition type and face, 5/8" Type X W.R. at the wet locations (A100 note 5) and the C-1 ceiling, metal corner bead, control joints (ASTM C840), tape and compound.

1c. FRP B-3 (A700): restroom to 4'-0" (A402) and mop sink alcove (1/A504) with edge, inside / outside corner and division bar trim (A700 B-3).

1d. Demolition of existing gypsum board and metal framing (D100 keynotes 9 / 27), by area (SF).

NOT INCLUDED / EXCLUSIONS:

• FRT plywood sheathing / substrate: wood (Div. 06): FRT plywood blocking at pendant lights (1/A501), 2X4 blocking between joists (6/A500), 3/4" FRT plywood
• Framed openings (MEP, access panels, diffusers): not in scope (estimator standing order, no RFI): framed openings for ducts / air devices; no access panel in gypsum surf
• Acoustical sealant / sound attenuation: EXCLUDED in all projects (estimator standing order): no acoustical sealant row and no quantity
• Wood framing / blocking / plywood (Div. 06): wood framing / blocking (Div. 06), not in scope: FRT plywood pendant blocking 1/A501, 2X4 blocking 6/A500, 3/4" FRT plyw
• Fasteners: screws, anchors, PAF: estimator standing order: drywall / framing screws, Hilti X-U shot pins (2/A500), #10 / #12-24 Tek screws (4/A500), anch
• Framed openings for ducts: estimator standing order: duct / air device openings never quantified (M101 / M501 swept).
• ACT ceilings and grid: C-2 ACT lay-in ceilings and grid (A200, A700).
• Existing ceiling demolition: D100 keynote 7 gypsum / ACT ceilings 'throughout': extent of each type not shown, excluded for lack of information (0 SF
• Insulation: batt insulation of type D (1/A500) and A100 note 7 insulation patching.
• Paint: paint PT-1..PT-4 (A700).
• Storefront, doors, frames, hardware: existing storefront (A300), doors / HM knockdown frames / hardware (A600): other trades.
• Millwork, slat wall, fixtures: millwork and fixtures by the millworker / owner (G001, A103); only the metal blocking behind them is ours.
• MEP and fire alarm: mechanical, plumbing, electrical, fire alarm / Starlink (M / P / E / FA sheets).
• insulation (batt, sound batt, rigid polyiso, rigid board): estimator standing order: insulation always EXCLUDED
• iPad backing plate 4/A104 ('BACKING PLATE BY G.C.')
• Existing ceiling demolition (D100 keynote 7) - for lack of information
• Bonds, permits and fees
• Temporary utilities, dumpster, prevailing wages, shop drawings
• Work at the existing 3-hour fire-rated demising wall: rated assembly, firestopping and permanent identification above the ceiling (A100, A200,

NOTE: PROPOSAL HOLDS GOOD ONLY FOR THE ITEMS AND QUANTITIES LISTED ABOVE (TAKE-OFF REV4 FINAL)

3.- Work Standard:

All work is to be completed in a workmanlike manner according to standard practices. Workers will remain on the job until completion of the project. The worksite will be cleaned daily and upon project completion. All agreements are contingent upon delays beyond our control.

4.- Limited Warranty:

The completed work shall carry a 1-year warranty on labor and materials. This warranty is in lieu of all other warranties, expressed or implied, and excludes consequential or incidental damages caused by accident or abuse, temperature changes, settlement, moisture, or cracks caused by expansion and/or contraction.

5.-	Insurance:
All employees are covered under blanket workman's comp, with liability and umbrella insurance policies.	

6.-	Touch-Ups:
Drywall & finishes: included on all work performed, limited to 1 hr per every 1,000 SF for quality issues; trade damage repairs tracked on work ticket. Finish level per GA-214 (Level 4).	

7.-	Others:
7.1. Work sequenced according to industry standards; out of sequence work and schedule delays require added cost. 7.2. Work days Monday - Saturday, 7:00 am - 5:00 pm (no overtime or night work included). 7.3. Price valid for thirty (30) days. Material pricing per FBM list prices read 11-05-2026.	

8.-	Demolition works:
	$3,300

9.-	Metal framing:
	$23,400
9.a- Drywall & drywall finish Level 4:	
	$14,500
9.b- FRP panels & trim:	
	$700
Total all trades:	
	$41,900
Taxes (8.81% template rate - to confirm for Centennial):	
	$3,691
Total including tax:	
	$45,591

**NOTE: items marked [RATE TO CONFIRM] / [PRICE TO CONFIRM] / allowances in the PRICING sheet are not in the

Acceptance of proposal:

The prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified.

Signature: _____

Date of

CLARIFICATIONS (decisions applied in the quantities):

RFI-01 (user decision 2026-11-05, option A, rule U-146): two printed deck heights and no drawn break - C3-01 studs to the higher printed deck 17'-1 9/16" (A100).

RFI-04 (user decision 2026-11-05, option A, rule U-147): no finish level printed - Level 4 on all gypsum board.

RFI-02 (rule BOTH SIDES): type A# '5/8" TYPE X ON EACH SIDE' (1/A500) - board on both faces.

RFI-06: restroom C-1 ceiling on the 2/A501 drywall grid suspension system (ICC ESR 1289).

RFI-03 / RFI-05 / RFI-07 / RFI-08: resolved with what the sheets print (2/A500, 3/A500, 4/A500, A100, 2/A400, A600 door 3C, 1/A504).

Demolition is priced by area (SF); existing walls to demolish carried to the printed B.O. structure (D100, A100).

Wood blocking / FRT plywood (Div. 06), fasteners, insulation, ACT, paint and MEP are excluded (see exclusions).

Material prices: FBM (myfbm.com) list prices read 11-05-2026; FRP trim priced with equal products (Marlite M370 / M360 / M350 not listed).

Addenda: Rev 2 Permit Set 11-04-2026 (city comments) and the architect / MEP response letters reviewed sheet by sheet - no change to partitions, board, ceilings or demolition; pricing unchanged.

Patch and repair at the removed electrical panels (D100 keynote 12, Rev 2) is inside the patch & repair allowance.