JC HUNTER
TECHNOLOGIES

3200 S. Wadsworth Blvd.
Lakewood. Col. 80227
Ph. 626 7789763
PROPOSAL

PROPOSAL SUBMITTED TO:	PER PLAN & SPECS:
Owen-Ames-Kimball Co. - Jess Matias	YES - 2026 Permit Drawings + Project Manual Vol 1 & 2
PROJECT NAME:	**ARCHITECT:**
CR CITY HOTEL (new 4-story hotel, Type IIIB, wood framed)	Meridian 105 Architecture
PROJECT ADDRESS:	**DATE OF PLANS:**
415 PERRY STREET, CASTLE ROCK, CO 80104	Arch. / Struct. 04-22-2026 (Issued for Permit); MEP 06-01-2026
DATE OF PROPOSAL:	**ADDENDUM:**
11-10-2026	None reviewed [TO BE CONFIRMED]
PHONE NUMBER:	**E-MAIL:**
[TO BE COMPLETED]	[TO BE COMPLETED]

Scope of Work:

We propose to supply the material, labor, and equipment necessary to complete the work in accordance with the plans

(Please take special note of the scope description; we are not required to perform any items or tasks not specifically listed)

1.- Division of work: DRYWALL & FINISH LEVEL 4, C-H SHAFT WALLS, CEILING SUSPENSION.

INCLUDED (quantities from the take-off rev15 FINAL: net and purchase = net + waste, with their sheets):
- 2-1/2" stud: 664.97 LF net / 764.72 LF purchase [1/A7.31, 7/A7.23, 1/A7.23, 1/A7.24, 7/A6.01, U-139 (+2 more)]
- Ceiling / soffit track (size per source, see Where it comes from): 2,616.04 LF net / 3,008.45 LF purchase [1/A7.31, 2/A7.31, 4/A7.31, 5/A7.31, 7/A7.31, 1/A7.23 (+7 more)]
- Carrying channel (ceilings): 167.56 LF net / 192.69 LF purchase [1/A2.02, 4/A5.05, 7/A7.23, 1/A3.02, 2/A7.05, 1/A2.03 (+9 more)]
- Hanger wire: 519.94 LF net / 597.93 LF purchase [1/A2.02, 4/A5.05, 7/A7.23, 1/A3.02, 2/A7.05, 1/A2.03 (+21 more)]
- 5/8" gypsum board, Type X: 87,650.77 SF net / 92,909.82 SF purchase [1/A5.06, 3/A7.45, 1/A5.08, 1/A7.30, 3/A5.04, 7/A7.31 (+113 more)]
- 5/8" gypsum board, Type X W.R. (water resistant): 28,073.50 SF net / 29,757.91 SF purchase [1/A2.02, 2/A7.00, 6/A7.00, 10/A7.00, 2/A7.05, 4/A7.05 (+75 more)]
- USG drywall suspension main tee DGLW26: 1,679.86 LF net / 1,931.84 LF purchase [1/A3.03, 1/A3.04, 2/A7.50, 3/A7.50, U-159]
- USG drywall suspension cross tee DGLW424: 5,039.70 LF net / 5,795.65 LF purchase [1/A3.03, 1/A3.04, 2/A7.50, 3/A7.50, U-159]
- USG angle molding DGWM24: 2,895.16 LF net / 3,329.43 LF purchase [1/A3.03, 1/A3.04, 2/A7.50, 3/A7.50, U-159]
- 5/8" cement board (tile base): 3,694.36 SF net / 3,916.02 SF purchase [1/A2.02, 6/A7.02, 8/A7.03, 9/A7.03, 1/A2.03, 1/A2.04 (+18 more)]
- Resilient channel - printed product (see Where it comes from): 19,691.55 LF net / 22,645.28 LF purchase [1/A2.02, 4/A5.05, 7/A7.23, 1/A3.02, 2/A7.05, 1/A2.03 (+16 more)]
- Alkali-resistant glass-fiber mesh tape at cement backer board joints - printed product (see Where it comes from): 1,366.92 LF net / 1,366.92 LF

purchase [A0.06]
• Setting-type joint compound at cement board joints - printed product (see Where it comes from): 266.00 LB net / 266.00 LB purchase [A0.06]
• METAL trim - corner bead, casing bead, shadow molding, gypsum edge trim: 4,010.68 LF net / 4,612.28 LF purchase [08/A9.05, 1/A8.02, 2/A8.02, 3/A8.02, 1/A7.31, 1/A7.23 (+14 more)]
• Control joint, gypsum board walls and ceilings (ASTM C840: walls 30 ft max, ceilings 50 ft max): 1,169.52 LF net / 1,344.95 LF purchase [1/A2.02, 1/A2.03, 1/A2.04, A2.01, A0.06, C840]
• 5/8" gypsum board, Type C (ceiling): 21,768.98 SF net / 23,075.12 SF purchase [4/A5.05, 3/S3.02, 2/A5.00, 1/A3.02, 1/A3.03, A3.01 (+4 more)]
• 1" gypsum shaftliner panel, Type X (C-H shaft wall): 1,388.71 SF net / 1,472.03 SF purchase [8/A9.03, 1/A5.08, 11/A9.03, 7/A9.03, 10/A9.03, 1/A7.50 (+12 more)]
• 5/8" exterior gypsum sheathing, Type X: 18,252.71 SF net / 19,347.87 SF purchase [08/A9.05, 8/A9.05, 6/A9.03, 5/A5.04, 1/A4.04, 5/A6.02 (+36 more)]
• C-H stud 2-1/2" 20 GA (shaft wall) - printed (see Where it comes from): 806.13 LF net / 927.05 LF purchase [7/A9.03, 8/A9.03, 1/A2.03, 1/A2.04, 1/A5.08, A2.02 (+4 more)]
• C-H stud 6" 20 GA (shaft wall) - printed (see Where it comes from): 763.13 LF net / 877.60 LF purchase [1/A5.08, 8/A9.03, 11/A9.03, 7/A9.03, 10/A9.03, A7.50 (+4 more)]
• J-runner 2-1/2" 20 GA (shaft wall top / bottom) - printed (see Where it comes from): 121.52 LF net / 139.75 LF purchase [1/A2.03, 1/A2.04, A2.02, A0.06]
• J-runner 6" 20 GA (shaft wall top / bottom) - printed (see Where it comes from): 155.71 LF net / 179.07 LF purchase [8/A9.03, 1/A5.08, 11/A9.03, 7/A9.03, 10/A9.03, A7.50 (+3 more)]
• Joint compound, all purpose: 8,491.14 LB net / 8,491.14 LB purchase [driver = the board / stud / bottom track rows of this sheet]
• Joint tape, paper: 50,872.50 LF net / 50,872.50 LF purchase [driver = the board / stud / bottom track rows of this sheet]
• Level 4 finish on all interior gypsum board (09 29 00 3.6.E.4); board only on the wood-framed walls (framing by others).

1a. Gypsum board on the WOOD-framed walls (framing by others, Div. 06): 5/8" Type X per face and layers per type and rating (A0.06, A0.07, UL U379 / U301 / U341 / V337), 5/8" Type X W.R. at toilet / shower / janitor faces (A0.06 GN 11 / 12), 5/8" cement board at guest bath tile walls (GN 13), 5/8" Type X glass-mat exterior gypsum sheathing, ASTM C1177 (06 16 00 2.5.B), per A0.07 XW rows.

1b. Ceilings: FS-1 5/8" Type C on resilient channel (A0.08, UL L546), RS-1 5/8" Type X on channel under the roof, GYP-1 / GYP-2 dropped ceilings on USG drywall suspension (main tee DGLW26, cross tee DGLW424, angle DGWM24, hanger wire), corridor bands, lobby coffers and stair soffit with ceiling / soffit track (7/A7.23, 2/A7.31, 11/A6.01).

1c. C-H shaft walls: L2-L4 north / south shafts 2-1/2" 20 GA C-H studs + 2-1/2" J-runner (7/A9.03, 8/A9.03 4 3/4" 2-HOUR SHAFTWALL W419 / U497); L1 / L4 chase 6" 20 GA C-H + 6" J-runner (CH.6, 1/A7.50); studs @ 24" o.c. to the liner height; 1" Type X shaftliner + 2 layers 5/8" Type X.

1d. Metal corner bead (09 29 00 2.5), control joints (A0.06 GN 15, ASTM C840), joint tape and compound, Level 4 finish.

NOT INCLUDED / EXCLUSIONS:

• Interior partition framing (studs + tracks): (Div. 06, R80f.1 / U-139). Metal framing only at C-H shaft walls (ALC-21).
• Exterior wall framing (CFMF): (Div. 06); interior board and exterior gypsum sheathing carried (ALC-07 / ALC-09).
• Parapet framing: (Div. 06); A0.01 / A0.02 / A8.02 parapet mentions are code / flashing.
• Headers, sills and jambs at openings: (Div. 06). Gypsum board returns at windows: see trim / returns.
• FRT plywood sheathing / substrate: wood (Div. 06): FRT plywood / LP Flameblock sheathing (A0.07, A0.08, A2.05, A7.30, A9.03, S5.01).
• Blocking (FRT wood / metal) for millwork and accessories: (Div. 06, U-139); no metal blocking printed.
• Framed openings (MEP, access panels, diffusers): framed openings for ducts / diffusers (standing order); no access panels in gypsum scheduled (A8.00, M1.01, M1.05, P4.00, P4.01, T0.01 legend).

(A8.00, M1.01, M1.05, P4.00, P4.01, T0.01 legend).
• Acoustical sealant / sound attenuation: EXCLUDED in all projects (estimator standing order): no acoustical sealant row and no quantity
• Wood framing / blocking / sheathing (Div. 06): wood studs, plates, trusses, blocking, FRT plywood, LP Flameblock (A0.06, A0.07, A0.08, S-sheets): Div. 06 (U-139).
• Fasteners: screws, anchors, PAF: estimator standing order (U-053).
• Framed openings for ducts / penetrations: estimator standing order (R-ALC-03).
• ACT / wood slat ceilings: ACT-1 / ACT-2 / ACT-3 lay-in and WS-1 wood slat ceilings (A3.01-A3.04, A7.23, A7.31): other trades.
• Insulation: batt / mineral fiber / rigid insulation (A0.06, A0.07, A0.08).
• Plaster / wallcovering / paint: TF-1 plaster, vinyl wallcovering, P-1 / P-2 paint (A7.19).
• CMU / concrete walls: CM.x CMU and C.x cast-in-place concrete walls (A0.06, A6.00-A6.02): masonry / concrete trades.
• Food & Beverage interiors (L1 Kitchen 100 / Dining, L4 410 / 411 / 419; BAR 107 except its printed ceiling): 'INTERIOR OF FOOD AND BEVERAGE SPACE IS NOT IN SCOPE OF THIS PERMIT. WILL BE SUBMITTED IN FUTURE TENANT IMPROVEMENT PERMIT.' (1/A2.04, A3.04, A7.45, A7.50, A7.55) + A0.00 'core and shell': non-rated faces and ceilings by the tenant; rated walls and the FS-1 / RS-1 rated membranes stay (RFI-05 criterion). Exception, BAR 107 ceiling: A5.04 'BAR SUSPENDED GYP CEILING' / 'CLG 11'-0"' and 3/A7.31 'SECTION - BAR CEILING' are printed -> loaded by R-ALC-10 (the specific drawing governs A0.00 'core and shell'), CLG-L1-125 125.98 SF; delta if the bar is F&B tenant work: -125.98 SF board + grid (RFI-22).
• Retail 124 tenant finishes: A2.01 '*NOTE: GYPSUM BOARD & FINISH IN RETAIL SPACE BY FUTURE TENANT': non-rated retail faces (incl. the sweep of every -0 wall: XW.6.4-L1-04, retail parts of XW.6.3-L1-01 and FI.2-L1-06) and the GYP-1 11'-0" band inside the retail (RFI-05).
• Separate-permit areas: grey toned area 'UNDER A SEPARATE PERMIT AND NOT IN SCOPE' (A2.01-A2.04); existing historic building (A0.00).
• Doors, frames, windows, hardware: A8.00 / A8.01 by others.
• Structural steel: kickers, clip angles, L3x3 angles: L3x3x1/4 KICKER at 4'-0" o.c. (S1.02, 5/S3.08) and CLIP ANGLE with threaded rods into masonry (S3.04, S3.08) are drawn and sized on the STRUCTURAL sheets (S1.02 'L3x3x1/4 KICKER AT 4'-0" O.C.', 5/S3.08 'L3x3 KICKER, SEE PLAN FOR SPACING' with '(3) 3/4" A325 BOLTS', S3.02 'L3x3x3/8 BRACE AT 4'-0" O.C.', S3.04 / S3.06 / S3.08 / S4.02 'CLIP ANGLE ... A36 THREADED RODS') = structural steel members (Div. 05 structural steel), not cold-formed / drywall framing: other trade (standing rule: structural members on S-sheets are not our scope).
• insulation (batt, sound batt, rigid polyiso, rigid board): estimator standing order: insulation always EXCLUDED
• Gypsum board & finish at the NON-rated retail-side faces of Retail 124 (A2.01 note 'BY FUTURE TENANT', RFI-05); (the L1 retail steel beam wraps of the rated FS-1 membrane ARE included, RFI-20)
• Area 'UNDER A SEPARATE PERMIT AND NOT IN SCOPE' (A2.01, RFI-06) and the existing historic building
• Screws, anchors, pins and power-driven fasteners (estimator standing order U-053)
• Level 5 finish in the base (Level 4 per 09 29 00 3.6.E.4; see ADD ALTERNATE AA-1), FRP, access panels (none scheduled for our trade)
• Bonds, permits and fees; temporary utilities, dumpster, prevailing wages, shop drawings
• Addenda not reviewed in this pricing; anything not specifically listed in the INCLUDED scope

CLARIFICATIONS:
• DA-4: XW.6.6-2 Level 4 interior face extension to the roof sheathing - not in base (04/A9.05 ends the board at the top plate) - not in the base, no price effect

ADD ALTERNATES:
• AA-1: Level 5 finish (skim coat over the whole surface, 09 29 00 3.6.D.5 / 3.6.E.5) on the exposed gypsum of the public areas (corridors, lobbies, stairs, vestibules) if they are painted (A7.19 'TF-1 ALT - WALLS / CEILINGS PAINT ALT') instead of 2-coat plaster; base = Level 4 [DERIVED: 18667.62 SF outer wall layer facing public areas + 3007.07 SF GYP-1 ceilings of public areas] - ADD 21,674.69 SF Level 5 skim coat

DEDUCT ALTERNATES (the base above carries the larger option while the RFI is open):
• DA-2 (RFI-24): DATA 118B west and east walls as tagged (W.6.1 | 0 / W.6-0) - DEDUCT 414.03 SF 5/8" Type X

NOTE: PROPOSAL HOLDS GOOD ONLY FOR THE ITEMS AND QUANTITIES LISTED ABOVE (TAKE-OFF REV15 FINAL)

3.- Work Standard:

All work is to be completed in a workmanlike manner according to standard practices. Workers will remain on the job until completion of the project. The worksite will be cleaned daily and upon project completion. All agreements are contingent upon delays beyond our control.

4.- Limited Warranty:

The completed work shall carry a 1-year warranty on labor and materials. This warranty is in lieu of all other warranties, expressed or implied, and excludes consequential or incidental damages caused by accident or abuse, temperature changes, settlement, moisture, or cracks caused by expansion and/or contraction.

5.- Insurance:
All employees are covered under blanket workman's comp, with liability and umbrella insurance policies.

6.- Touch-Ups:
Drywall & finishes: included on all work performed, limited to 1 hr per every 1,000 SF for quality issues; trade damage repairs tracked on work ticket. Finish level per GA-214 (Level 4).

7.- Others:
7.1. Work sequenced according to industry standards; out of sequence work and schedule delays require added cost. 7.2. Work days Monday - Saturday, 7:00 am - 5:00 pm (no overtime or night work included). 7.3. Price valid for thirty (30) days. Material pricing per FBM list prices read 11-05-2026.

9.- Metal framing (C-H shaft walls) & ceiling suspension:	
	$48,700
9.a- Drywall & drywall finish Level 4:	
	$426,900
Total all trades:	
	$475,600
Taxes (8.81% template rate - to confirm for Castle Rock):	
	$41,900
Total including tax:	
	$517,500

****NOTE: items marked [RATE TO CONFIRM] / [PRICE TO CONFIRM] in the PRICING sheet are not in the totals.**

Acceptance of proposal:

The prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified.

Signature: _____

Date of

CLARIFICATIONS (decisions applied in the quantities):

Wood-framed building: all W / FW / DW / FI / XW types are wood studs (A0.06, A0.07) - board only; framing, blocking, FRT plywood by Div. 06.

RFI-10: WOOD / FURRED WOOD / DBL. WOOD sections print 5/8" TYPE X GYP BD. TYP. - Type X loaded on every interior face (09 29 00 2.3 A).

RFI-11: cement board at guest bath tile walls to 9'-0" (bath ceiling 8'-6" + 6"); rated Type X W.R. layers stay full height.

RFI-07: L2-L4 shaft walls carried with 2-1/2" C-H per 7/A9.03 / 8/A9.03 (4 3/4" assembly); A0.06 CH.6-2 prints 6" - same LF in 6" if required.

RFI-16 / RFI-14: C-H studs @ 24" o.c. (UL U415); resilient channel @ 16" o.c. (UL L546, 'spacing per assembly').

RFI-12: GYP-1 'metal suspension OR wood framing' - metal option carried (USG drywall suspension).

RS-1 ceilings under the roof: board type not printed - 5/8" Type X carried; channel carried in the resilient channel row.

RFI-05: retail faces of RATED assemblies stay loaded (1,033 SF); non-rated retail faces excluded (532.5 SF, by future tenant).

RFI-18: L4 corridor 412 cove carried along the corridor walls (typical 7/A7.23); L1 lobby ceiling carried at 11'-0", no step face.

Material prices: FBM (myfbm.com) list prices read 11-05-2026; exterior sheathing = 5/8" Type X glass-mat gypsum sheathing, ASTM C1177 (06 16 00 2.5.B); FBM glass-mat SKU [PRICE TO CONFIRM].